Items of work.	*Per.*	*Lower storey.*	*Upper storey.*
Cornice 1½′ deep	R. ft.	718	.
Do 1′ do	Do	2,708	2,598
Do 7½″ do	Do	1,510	..
Key stone moulding to arches	E	51	..
Cut stone work for steps	S. ft.	1,025	..
Slab stone templates	Do	180	..
Do	Do	..	107
Cast iron columns 13′ high 6″ at top and 7½″ at bottom	E	6	..
Dental cornice 1½′ deep including architrave moulding	R. ft.	..	927
Mangalore tile roofing	Sqr.	..	85·60
Ionice columns with pedestal base and capital complete 19′ high	E	..	60
Balustrading parapets	R. ft.	..	294
Parapet at top of building	Do	..	786
Terrace roofing	Sqr.	..	66·84
Iron rod for truss, &c.	lbs.	..	68·55
Central staircase	E	.	1
End staircase	Do	..	2
Servant staircase	Do	..	2
Planking to footboard	S. ft.	..	2·45
Teak wood work to footboard	C. ft.	..	10
Hand railing do	R. ft.	..	64
Cast iron ridging with crusting	Do	..	280
Do ornamental ridging	Do	..	246
Plank ceiling 1½″ for tower and side wards	Sqr.	..	70·22
Pediment above ventilators	R. ft.	..	1,054
For sham windows, imitation, balustrading and plinth moulding		Lump sum.	
School of Arts tile roofing	Sqr.	..	77·52
White and colour washing	Do	387·0	..
Do do	Do	..	552·0
Bamboo matting	Do	..	19·88
Drainage pipe		Lump sum.	
Cast iron shoes, clamps, plates, bolts, and other iron works for roofing of tower and trusses		Do	
Cast iron ornamental finials		Do	
Scaffolding for towers		Do	
For ornamental moulding for superstructure on main pediment		Do	
Cloth ceiling	Sqr.	..	17·60

NOTICE.

The particular attention of contractors and others who intend submitting their tenders for the construction of the Administrative Block of the General Hospital at Bangalore is invited to the specification for work in the several parts of the walling available in the Executive Engineer's office, Bangalore division. The plans of the building may be seen at the Chief Engineer's office on all office days between the hours of 7 to 10 A. M.

2. Any further information as to details of work will be supplied on application at the Executive Engineer's office.

B. S. VENKATACHARIYAR, *Executive Engineer.*

TUMKUR DIVISION.

NOTICE.

The undermentioned arrears due to contractors, noted against each item, are outstanding in the accounts of the division from a long time. Notice is hereby given that the persons named herein should either present themselves in person or by their authorized agents, on or before the 30th of April 1897, before the Executive Engineer, Tumkur division, to receive the payment. Failing to do so, the amount will be credited to Government as unclaimed arrears and no complaint of non-payment will then be entertained.

Name.	*Amount.* Rs. A. P.	*For what work due.*
1. Somappa	4 7 9	Constructing musafirkhana at Nagalnadike, Pavagada taluk.
2. Mullakhan	73 12 1	Do do at Dodaguni.
3. Govinda Rao	2 0 0	Opening out Pavagada-Roddam road.

C. T. DALAL, *Exec. Engr.*